

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21285-00-00
Spot: SWNENE Sec/Twnshp/Rge: 20-9S-25W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: ROME Well #: 2
County: GRAHAM Total Vertical Depth: 2285 feet

Operator License No.: 4335
Op Name: TERROL ENERGY, INC.
Address: PO BOX 246
HYGIENE, CO 80533

PROD Size: 4.5 feet: 2285 500 SX CMT
SURF Size: 8.625 feet: 233 190 SX CMT

\$74²⁴

Well Type: SWD UIC Docket No: D20058.0 Date/Time to Plug: 06/08/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY ENRIGHT Company: TERROL ENERGY, INC. Phone: (303) 772-7819

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel - 700# hulls.
Failed MIT - casing leaks - not isolated.
PBSD 2045'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2005 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 51 joints of 2 3/8" tubing to 1580'.
Swift Services pumped 85 sxs 60/40 pozmix - 10% gel with 500# hulls - cwc.
PTOH. Swift squeezed with 15 sxs cement.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to backside and pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2000 | 2040 | | |
| 1927 | 1957 | | |
| 1830 | 2020 | | |

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

RECEIVED

DATE

6-16-05

JUN 15 2005

TRAIL NO.

200SD/1834

KCC WICHITA

JUN 13 2005

