

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20200-00-00  
Spot: SESW Sec/Twnshp/Rge: 2-17S-24W  
660 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: HORCHEM D Well #: 4  
County: NESS Total Vertical Depth: 4485 feet

Operator License No.: 32754  
Op Name: ELYSIUM ENERGY, L.L.C.  
Address: 1625 BROADWAY, SU 2000  
DENVER, CO 80202

PROD Size: 5.5 feet: 4471 WITH 75 SX CMT  
SURF Size: 8.625 feet: 225

#14576

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/10/2005 10:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OIL FIELD SERVICE, INC.  
Proposal Rcvd. from: JERRY WIRTZ Company: ELYSIUM ENERGY Phone: (303) 592-8600

Proposed Plugging Method: RUN TUBING TO 4300' & PUMP 35 SX CMT & 200# HULLS. PULL TUBING TO 1700' & PUMP 50 SX CMT. PRESSURE TEST. PERFORATE @ 950' PUMP 160 SX CMT. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/10/2005 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:


HOLES @ 2400'. RAN TUBING TO 4300' & PUMP 35 SX CMT WITH 200# HULLS. PULL TUBING TO 1700' & PUMP 50 SX COMMON CMT WITH 3% CC. WAIT 2 HOURS. PRESSURE CASING TO 500#. PERFORATED AT 950' & PUMP 160 SX CMT. MAXIMUM PRESSURE 500#. PUMP 150 SX CMT DOWN BACKSIDE. MAXIMUM PRESSURE 250#. SHUT IN PRESSURE 100#.

INVOICED  
DATE 6-21-05  
INV. NO. 2005061842

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT W/3% CC BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael J Maier  
(TECHNICIAN)

RECEIVED  
JUN 21 2005  
KCC WICHITA

Form CP-208