

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20111-00-00
Spot: NWSW Sec/Twnshp/Rge: 2-17S-24W
2000 feet from S Section Line, 4605 feet from E Section Line
Lease Name: HORCHEM D Well #: 1
County: NESS Total Vertical Depth: 4545 feet

Operator License No.: 32754

PROD Size: 5.5 feet: 4543 WITH 75 SX CMT

Op Name: ELYSIUM ENERGY, L.L.C.

SURF Size: 8.625 feet: 221

Address: 1625 BROADWAY, SU 2000
DENVER, CO 80202

147'

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/09/2005 12:00 PM

Plug Co. License No.: 32970

Plug Co. Name: H-D OIL FIELD SERVICE, INC.

Proposal Rcvd. from: JERRY WIRTZ

Company: ELYSIUM ENERGY

Phone: (303) 592-8600

Proposed Plugging Method: RUN TUBING TO 4300' & PUMP 70 SX CMT WITH 400# HULLS. PULL TUBING TO 1800' & PUMP 40 SX CMT. PRESSURE TEST CASING. PERFORATE AT 950' & PUMP 160 SX CMT. PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/09/2005 4:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

RUN TUBING TO 4300' & PUMP 70 SX CMT WITH 400# HULLS. HOLES IN CASING FROM 4023-3678'. PULLED TUBING TO 1800' & PUMPED 40 SX COMMON CMT W/3% CC. WAITED 1 1/2 HOURS. PRESSURED CASING TO 500# AND HELD. PERFORATED AT 950'. PUMPED 160 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 200#. PUMPED 40 SX CMT DOWN BACKSIDE. PRESSURED TO 500# & HELD.


Top	Bot	Thru	Comments
4485	4489		
4264	4271		

INVOICED
DATE 6-21-05
I.V. NO. 2005061842

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT W/3% CC BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

RECEIVED

JUN 21 2005

KCC WICHITA

Form 01-25