

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20080-00-00
Spot: NESW Sec/Twnshp/Rge: 5-22S-33W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: GARDEN CITY B Well #: 9
County: FINNEY Total Vertical Depth: 4799 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

CIBP Size: feet: 1188
PROD Size: 7 feet: 4799 WITH 100 SX CMT
SURF Size: 9.625 feet: 430 WITH 450 SX CMT

\$155.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2005 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 277-2511

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/10/2005 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT & 300# HULLS AT 4329' THROUGH 2 7/8" TUBING. FULL CIRCULATION WHILE SPOTTING PLUG. SET CIBP @ 1188'. LOADED 7" CASING WITH 17 BBL WATER AND TEST CASING TO 500 PSI. HELD OK. PERFORATE AT 1150'. PUMPED INTO PERFS AT 700#. PUMP 130 SX CMT AND DISPLACE WITH WATER LEAVING 30 SX CMT IN THE 7" CASING. FINAL PUMP IN PSI = 2 BPM @ 1000 PSI. INITIAL SHUT IN PRESSURE 550#. NO BLOW OR RETURNS OUT 7" X 9 5/8" ANNULUS. SPOT 50 SX CMT @ 490 THROUGH TUBING. GOOD CIRCULATION. SPOT 15 SX CMT AT 40' TO SURFACE THROUGH TUBING. GOOD CIRCULATION. PUMP 200 SX CMT DOWN 7" X 9 5/8" ANNULUS AT 3 BPM @ 350#. INITIAL SHUT IN PRESSURE 150#.

Perfs:


Top	Bot	Thru	Comments
4702	4714		
4402	4410		
4380	4384		

INVOICED
DATE 6-21-05
IN NO. 2005061843

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
JUN 21 2005
KCC WICHITA

[Signature]
Form CR-2/3