

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-12660-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 17-21S-12W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HEATON Well #: 1  
County: STAFFORD Total Vertical Depth: 3528 feet

Operator License No.: 3941  
Op Name: LOGAN, LESLIE DBA L. B. OIL  
Address: 211 - 8TH STREET  
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3523 100 SX CMT  
SURF Size: 8.625 feet: 267 175 SX CMT

*4114<sup>66</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2005 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS PLUGGING REPORT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/14/2005 4:48 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 666'. CASING IN BAD SHAPE 659' DOWN. PERFORATED 5 1/2" CASING @ 658'. SPENT 4 HOURS WORKING & DRILLING TUBING TO 1613'. PUMPED PLUGS THROUGH TUBING. 1ST PLUG AT 1613' WITH 100 SX CMT. 2ND PLUG AT 660' WITH 420 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. 3RD PLUG AT PULLED TUBING OF BOTH STRINGS OF PIPE WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3421	3425		
3401	3404		
3339	3343		
3322	3330		
3284	3287		

**INVOICED**  
DATE 6-21-05  
INV. NO. 2005061844

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED  
JUN 21 2005  
KCC WICHITA

Form CP 2/3 *[Signature]*