

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10022-00-01
Spot: NENE Sec/Twnshp/Rge: 2-33S-30W
666 feet from N Section Line, 661 feet from E Section Line
Lease Name: STEVENS (MORROW) UNIT Well #: SMU-201
County: MEADE Total Vertical Depth: 5810 feet

Operator License No.: 32198
Op Name: PETROSANTANDER (USA) INC.
Address: 6363 WOODWAY STE. 350
HOUSTON, TX 77057

PROD Size: 5.5 feet: 5806 WITH 105 SX CMT
SURF Size: 8.625 feet: 1599 WITH 900 SX CMT

#188⁸³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/08/2005 10:30 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: PETE KUNEYL Company: PETROSANTANDER Phone: (620) 275-2388

Proposed Plugging Method: PULL 5-1/2" CASING TO APPROX. 2500', PULL @ 1600'W/50SX CMT. PLUG @ 600' W/40 SX CMT, PLUG @ 40' W/10 SX CMT. PLUG @ SURFACE W/10 SX.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2005 12:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

PUMP 400# HULLS & 30 SX CMT DISPLACED TO BOTTOM WITH 32 BBL OF MUD. TBG SET @ 5567'. PRESSURED CASING TO 300#. 1ST PLUG AT 1520' WITH 50 SX CMT DISPLACED WITH 25 BBL MUD. 2ND PLUG PULL OUT OF HOLE TO 600'. 6/9/05: LOAD HOLE & SPOT 50 SX CMT AT 600'. 3RD PLUG PULL OUT OF HOLE TO 40' & PUMP 15 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5667	5695		

INVOICED
DATE 6-21-05
BY 2005061845

Remarks: USED 60/40 POZMIX BY EAGLE WELL SERVICE. RECOVERED 1558' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Gregory G. Patterson
(TECHNICIAN)

RECEIVED

JUN 21 2005

KCC WICHITA

Form CP-2/8