

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00812-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 25-12S-22W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: OGALLAH UNIT Well #: 7-3  
County: TREGO Total Vertical Depth: 4010 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3979 175 SX CMT  
SURF Size: 8.625 feet: 498 370 SX CMT

# 130<sup>33</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2005 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sxs cement and 600# hulls.  
Perforated at 920' and 1750'.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2005 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2200' - spotted 100 sxs cement with 200# hulls.  
Pulled tubing to 1100' - circulated with 55 sxs cement and 200# hulls.  
Pulled all tubing - squeezed 5 1/2" casing with 135 sxs cement and 200# hulls.  
Max. P.S.I. 600#. S.I.P. 400#.  
Tied to 8 5/8" x 5 1/2" annulus - squeezed 10 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.  
Total of 300 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
0			

Remarks: LEASE ALSO KNOWN AS CHURCH OF OGALLAH #3. ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger & Moses  
(TECHNICIAN)

INVOICED

DATE 6-21-05

INV. NO. 2005061847

RECEIVED

Form CP-2/3

JUN 21 2005

KCC WICHITA

JUN 15 2005

TEXAS COMPANY

#3

CHURCH OF OGALLAH NE SW SW

25-12-22W

TREGO

County

Contr.

E 2329RB

Comm.

Comp.

1-11-52

IP

3000 BOPD (ARB)

DRAW DOWN

Tops	Depth	Datum
HEEB	3563	-1234
LANS	3590	-1261
ARB	3982	-1653
T.D.	4010	-1681

Casing

5" 3979

DP 4010

OGALLAH POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS