

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01388-00-00
Spot: NESWNW Sec/Twnshp/Rge: 36-12S-22W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 11-4
County: TREGO Total Vertical Depth: 3991 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3953 175 SX CMT
SURF Size: 8.625 feet: 523 325 SX CMT

129 71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2005 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2450

Proposed Plugging Method: Ordered 350 sxs cement and 600# hulls.
Perforated at 920' and 1750'.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2005 5:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2200' - spotted 100 sxs cement with 200# hulls.
Pulled tubing to 1100' - circulated with 100 sxs cement and 200# hulls.
Pulled all tubing - squeezed 5 1/2" casing with 115 sxs cement and 200# hulls.
Max. P.S.I. 500#. S.I.P. 400#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed with 15 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.
Total of 330 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
0			

Remarks: LEASE ALSO KNOWN AS SCOTT #4. ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger A Moses
(TECHNICIAN)

INVOICED

DATE 6-21-05

INV. NO. 2005D61847

RECEIVED

JUN 21 2005

KCC WICHITA

Form CP-2/3

JUN 15 2005

017 117
 DYAN
 11 11 11

TEXAS COMPANY #4 SCOTT 36-12-22W
 NE SW NW

Contr. _____ TREGO _____ County

E 2311RB Comm. _____ Comp. 1-18-52 IP 311 BOPD

Tops	Depth	Datum
TOP	3345	-1034
HEEB	3545	-1234
LANS	3579	-1268
ARB	3951	-1640
T.D.	3991	-1680

Casing
 8" 523 CORRECTED CARD
 5" 3953 2-1-52

OGALLAH POOL

+	+	+	+
+	+	+	+
+	+	+	+
+	+	+	+

CORRECTED SPOT

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS