

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-30098-00-00  
Spot: NWSESW Sec/Twnshp/Rge: 21-21S-12W  
990 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: GROW Well #: 2  
County: STAFFORD Total Vertical Depth: 3668 feet

Operator License No.: 5141  
Op Name: ZENITH DRILLING CORPORATION  
Address: PO BOX 780428  
WICHITA, KS 67278

PROD Size: 5.5 feet: 3667 WITH 175 SX CMT  
SURF Size: 8.625 feet: 278 WITH 250 SX CMT

*A119<sup>21</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2005 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 350' & 5 SX CMT. PERFORATE AT 700'. PUMP 125 SX CMT TO CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/16/2005 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3520' & 5 SX CMT WITH BAILER. PERFORATED 5 1/2" AT 700'. RAN TUBING TO 710' TO PLUG THROUGH. PUMPED 125 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2" & 5 1/2" X 8 5/8" ANNULUS. PULLED TUBING. PRESSURED 5 1/2" TO 300 PSIG WITH 20 SX CMT. SHUT IN WITH 300 PSIG.

Perfs:


Top	Bot	Thru	Comments
3630	3630		
3593	3597		
3586	3590		
3570	3582		

**INVOICED**  
DATE 6-21-05  
INV. NO. 2005061850

Remarks: SUED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
JUN 21 2005  
KCC WICHITA

Form CP-28