

4-031700

6-8-92

90
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,424 -00-00

E2 SE SE /4 SEC. 11, 07 S, 21 W
660 feet from S section line
330 feet from E section line

Operator license# 4767

Lease Benoit well # 1

Operator: Ritchie Exploration, Inc.

County Graham

Address: 125 N. Market
#1000
Wichita, Kansas 67202

Well total depth 3662 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 216 feet

119.01

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 8 Month: June Year: 92

Plugging proposal received from: Pete

Company: Ritchie Exploration, Inc. Phone:

Were: Order 300 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company. Hole open to perf's.

RECEIVED

KANSAS CORPORATION COMMISSION

JUL 2, 1992
JUL 2 1992

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:30 P.M., Day: 8, Month: June, Year: 92

Actual plugging report: 8 5/8" set @ 216' w/160 sx. 4 1/2" set @ 3661'
w/125 sx. P.B.T.D. 3658'. Perf's 3382' - 3651'. Port collar @ 1752'
w/500 sx. cwc. cement fell to 600' by log. Mixed and pumped down
4 1/2" casing 225 sx. cement blend with 400# hulls mixed in to max.
P.S.I. 1000#. Close in P.S.I. 800#. Squeezed 8 5/8" with 75 sx. cement
blend with 100# hulls mixed in to max P.S.I. 400#. Close in P.S.I. 200#.
Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Carl Goodrow

DATE 7-8-92

WV. NO. 35637

HD

(agent)

Form CP-2/3