

1-4-92

59  
R

4-070976

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,658 - 00-00

NE NW SE /4 SEC. 08, 07 S, 21 W  
2310 feet from S section line  
1650 feet from E section line

Operator license# 5004 Lease Warden well # 1

Operator: Vincent Oil Corporation County Graham

Address: 100 No. Main Suite 500 Well total depth 3700 feet 120.25  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Julie Stout Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Inc. License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 4 Month: January Year: 92

Plugging proposal received from: Lloyd Dellete

Company: Murfin Drilling Company Phone: 316-262-3573

Were: 8 5/8"-217' S.P. cwc w/190 sx. 60/40 pozmix - 3% gel. -  
2% c.c. By B.J. Services. Elev. 2114' - Anhy. 1769' - (No cir.problems)  
Mud condition 45 vis. - 9.2 wt. - 9 W.L. Proposal 225 sx. 60/40 pozmix -  
6% gel. - 1 sx. flocele. Spot with drill stem, mud between all plugs.  
25 sx. @ 3600' - 25 sx. @ 1780' - 100 sx. with 1 sx. flocele @ 939' -  
40 sx. @ 270' - 10 sx. @ 40' - 15 sx. in Rathole - 10 sx. in Mousehole.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:30P.M. Day: 4 Month: January Year: 92

Actual plugging report: Murfin Drilling ordered 200 sx. 60/40 pozmix -  
6% gel. - 3% c.c. and 1 sx. flocele. Circulated hole. Spotted and  
displaced cement through drill stem.

1st. plug 25 sx. cement @ 1780'.  
2nd. plug 100 sx. cement @ 939' with 1 sx. flocele.  
3rd. plug 40 sx. cement @ 270'.  
4th. plug 10 sx. cement @ 40'.  
15 sx. in Rathole. 10 sx. in Mousehole.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 16 1992  
JAN 16, 1992  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: Operator said no ar buckle. Has not found Rick Hiebsch.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 2114 GL

I did  did not  observe the plugging.

*Marion J. Schmidt*  
(agent)

Form CP-2/3

**INVOICED**  
DATE FEB 01 1992  
INV. NO. 34445

*J. S.*