

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-179-05159-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 - 1966
05-04-1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Knight Casing Pulling Company,
Complete Address: Box #405, Chase, Kansas.
Lease Name J. E. Leonard Well No. 4
Location CSW-SE-NW Sec. 12 Twp. 6 Rge. (E) (W) 27
County Sheridan Total Depth 3899
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No. 436
Operation Completed: Hour 3:00PM Day 27 Month 4 Year 1966

The Above well was plugged as follows:

280'--8 5/8" Surface pipe, cement circulated with 280 Sx.
3897'--6" OD Production casing cemented with 300 Sx. No perforations.

Sanded well back to 3850 and set 5 Sx. cement with dump bailer.

Pulled 6" to 600' and circulated heavy gel mud (used 20 Sx. gel).

Pulled 6" to 540' and displaced 20 Sx. cement thru 6". Pulled 6" to
200' and displaced 20 Sx. cement thru 6". Pulled 6", set rock bridge
at 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. A. Nichols*
Well Plugging Supervisor

DATE 5/4/66
INV. NO. 3158-W