



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-052600000

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1974
12-9-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Company,

Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name Adell L-KC Unit Well No. 101

Location NE-NE-SE Sec. 11 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3885'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 1462

Operation Completed: Hour 3:00 PM Day 2 Month 12 Year 1974

The above well was plugged as follows:

240'---10 3/4" Surface casing, cement circulated with 240 Sx.
 3883'---6" OD Production casing cemented on bottom with 300 Sx. Well plugged back to 3859'. Top of perforations @ 3636'.

Pushed plug to 3630', sanded well back to 3590' and set 5 Sx. cement with dump bailer.

Pulled 6" casing and squeezed well initially with 5 sacks hulls and 17 sacks gel following with 135 Cu. Ft. cement from 1325' to 1000' then 22 sacks gel from 1000' to 260' and followed with 40 Cu. Ft. cement from 260' to 180' then 6 sacks gel from 180' to 30' and finally 15 Cu. Ft. cement from 30' to base of cellar. Maximum pump-in pressure-150#. Final Shut-in pressure-100#. (Mudding & cementing by Sun Oil Well Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. G. Nichols
Well Plugging Supervisor

INVOICED
DATE 12/10/74
INV. NO. 431-W