

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-05262-00-00

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
1-9-78
JAN 09 1978
(of this Division well)
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Co.

Complete Address 3535 NW-58th St. Okla. City Okla.

Lease Name Adell Lansing KC Unit Well No. 510

Location SE-NF-NW Sec. 11 Twp. 6 Rge. 27 (E) (W) 4

County Sheridan Total Depth 3840

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A 1

Other well as hereafter indicated _____

Plugging Contractor Kelso. Casing Pulling.

Address Box 176 Chase Ks. License No. 683

Operation Completed: Hour 10:00 AM Day 4 Month Jan. Year 1978

The above well was plugged as follows:

KB. 2594, Dak Top. 1400' S.P. 10 3/4 - 304' cwc. 300 sx.
6" Oil String. Set @ 3839 - w/300 sx. Top Per S. 3585'
Push. Bottom Plug. to 3580' w/sand + 4 sx. cem. com.
Pumped down. S.P. - 4 sx. Halls. 70. sx. cem. 50/50 Permiv
6% Gel. 17 sx. Gel. Release Plug. + 110 sx. cem. 50/50
Por. 6% Gel. Max. Pres. 400 lbs. Closing Pres. 300 lbs.
By. Sun. Cementing. Recovered. 1099' of 6" Casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-10-78
NO. 6548-W

Signed: [Signature]
Well Plugging Supervisor