

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-08265-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1976  
8-76  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Continental Oil Co.

Complete Address 3535 NW-58<sup>th</sup> St. Okla City, Okla.

Lease Name Adell Lansing KC. Unit. Well No. 306

Location C-SE-NE-NE Sec. 11 Twp. 6 Rge. 27 (E) (W)

County Sheridan Total Depth 3831

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 128 Ellen Wood Kansas. License No. 462.

Operation Completed: Hour 5:00 PM Day 5 Month Jan Year 1976

The above well was plugged as follows:

KB. 2631' Dak. Top. 1500' SP. 281' of 10 3/4 C.W.C. 300 sx. cem  
6" casing, set. w/300 sx. cem. Plug Back. 3831'  
Perf. 3415' to 3818' Bottom Plug to 3575  
w/sand + 5 sx. cem. cem. Recovered 1030' of 6" casing.  
Pumped down. 10 3/4 S.P. 5 sx. Halls, + 80 sx  
Cem. 50/50 Poz mix 6% Gel. 15 sx Gel. Release Plug.  
+ 90 5x. Cem 50/50 Poz mix 6% Gel. Closing Pres. 400 Lbs.  
Max Pres. 400 Lbs. Sun. Cementing.

I hereby certify that the above well was plugged as herein stated.

Signed: J. L. Butthorn  
Well Plugging Supervisor

INVOICED

DATE 1-8-76

INV. NO. 2539-W