

PL
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
DEC 10 1974
DEC 10, 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers-KSB&T Bldg., Wichita, Kansas 67202

Lease Name Sprick Well No. 1

Location W/2 NW NW Sec. 23 Twp. 7 Rge. (E) (W) 19

County Rooks Total Depth 3396'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 10 A Day 9 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3396' 8 5/8 csg set at 106' cwc 90 sk.

5 1/2 csg set at 3396' cw 100 sk. & perf. (3262-3266)

Filled 5 1/2 csg W/sd (3396-3250) Dumped 5 sk cmt W/dump bailer. (3250-3215)

Cutoff & recovered 840' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls -70 sk cmt -8 sk gel & water -released 8 5/8 plug & pumped 50 sk cmt by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/10/74
INVOICE NO. 437-W-

Signed: Robt. Massey
Well Plugging Supervisor