

4060021

10-9

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-23,054-00.020
NW SE SW, SEC. 23, T 7 S, R 20 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market Suite 1000
Wichita, KS 67212

990 feet from S section line
3630 feet from E section line

Lease Name Jackson Well # 1
County Rooks 114.27

Well Total Depth 3516 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 6:30PM Day: 9 Month: October Year: 19 89

Plugging proposal received from Lloyd Dellett

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Space all plugs with heavy drilling mud through drill pipe.

Order 205 sxs. 60/40 pos 6% gel 1/4# floccel per sx.

RECEIVED
OCT 30 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXXXX

Operations Completed: Hour: 6:30PM Day: 9 Month: October Year: 19 89

- ACTUAL PLUGGING REPORT
- 1st plug at 3480' with 20 sxs. Arbuckle at 3482'
 - 2nd plug at 1575' with 20 sxs. Anhydrite 1556-1583'
 - 3rd plug at 900' with 100 sxs. Dakota 599-899'
 - 4th plug at 265' with 40 sxs. Surface pipe to 216'
 - 5th plug at 40' with 10 sxs. With wiper plug
 - rathole plug with 15 sxs.

Remarks: Allied Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 11-2-89
INV NO 2631
10-9

Herb Deines

Signed Herb Deines
(TECHNICIAN)
Herb Deines