

6010158

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22421-00-00

NE, SEC. 23, T 7 S, R 20 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6176

Lease Name Wheeler Well # 2

Operator: Ivan Holt Well Svc.

County Rooks

Name & Address Box 401

Well Total Depth 3529 114.69 feet

Russell Ks.

Conductor Pipe: Size _____ feet

67665

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Revlin Drlg License Number 5671

Address Box 293 Russell Ks.

Company to plug at: Hour: PM Day: 1 Month: 7 Year: 19 84

Plugging proposal received from Stan Lingreen

(company name) Revlin Drlg. (phone) 913 483 5355

were: order 185 sx. cement 50/50 pozmix 6% gel. 3% col. cl.
1 sx hulls 7.8 5/8 plug 1 sx. flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2036 Anhydrite 1559-92- Arbuckle No.

Dakota. 1400 Plugging Proposal Received by Dale Balthazor
636 = 940 (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ (None)

Operations Completed: Hour: 4:30 PM Day: 1 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1570 for 10 mi.

25 sx @ 1570

100 sx @ 940 mixed with 1sx. flow seal

40 sx @ 350 dumped 1sx hulls pushed plug to 40'

10 sx @ 40

10 sx in Bat Hole

Remarks: cementing Co. State Corporation Commission
(If additional description is necessary, use BACK of this form.)

I did (not) observe this plugging July 09 1984

DATE 7-18-84 CONSERVATION DIVISION Dale Balthazor
Wichita, Kansas (TECHNICIAN)

INV. NO. 2552 AUG 3 1984 FORM CP-2/3 Rev. 01-84

July 6 84
21