

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-125-D 1165-00-00
SW SW SE Sec/Twp/Rge S 15 T34S R15E
204 GPS feet from south section line
2397 GPS feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Hester 2 Legacy Well # 35-812 35County MGOperator: State Of Kansas Fee FundWell Total Depth 480 (est) feetName & Hester 2 Lease ProjectProduction Pipe: 2 Size Feet 480 (est)

Address _____

Surface Casing: 10 Size Feet N/AAB oil well XXXXXX Gas Well _____

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well ServiceLic. # 30670Address: 19245 Ford Road, Chanute, KS 66720Company to plug at: _____ Hour: _____ Day: 14 Month: 4 2005

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: _____

Plugging Proposal Received by: _____

Alan M. Dunning

Plugging attended by Agent: _____

All _____

Part _____

TECHNICIAN

None XXXXXX

Operations Completed: Hour: _____

Day: _____

14

Month: _____

4

2005

Actual Plugging Report: _____

Run 0.75 inch cement string inside the 2 inch pipe to 445 ft and wash to450 ft. Run 1 inch cement string outside the 2 inch to 325 ft and wash to 335 ft. The well was plugged frombottom to top using 218 sacks of portland cement. The well was cut off below plow depth and the locationrestored.

RECEIVED

MAY 11 2005

KCC WICHITA

Remarks: Control # 20050002-047 Contract # 7641 The GPS well # is 47

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: _____

Alan M. Dunning
TECHNICIAN