

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23985-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 6-15S-18W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DECHANT WALTER Well #: 1
County: ELLIS Total Vertical Depth: 3602 feet

Operator License No.: 33457
Op Name: DECHANT, WALTER DBA DECHANT O
Address: 503 WEST 30TH STREET
HAYS, KS 67601

PROD Size: 5.5 feet: 3599
SURF Size: 8.625 feet: 483

4117⁰⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2005 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: WALTER DECHANT Company: DECHANT OIL COMPANY Phone: (785) 625-5281

Proposed
Plugging
Method:

Ordered 195 sxs cement - 600# hulls - 20 sxs gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/16/2005 12:45 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 3398' - spotted 20 sxs gel with 200# hulls, followed with 50 sxs cement and 200# hulls.
Pulled tubing to 1500' - circulated with 120 sxs cement and 200# hulls.
Pulled all tubing - squeezed with 10 sxs cement - blew hole in top of surface pipe at 400# P.S.I.
No S.I.P. (squeezing casing and surface pipe simultaneously.)
Total of 180 sxs 60/40 pozmix - 10% gel - 600# hulls and 20 sxs gel.

INVOICED
DATE 6-22-05
NO. 2005061852

Remarks: ALLIED CEMENTING COMPANY. HERTEL TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

RECEIVED

JUN 22 2005


KCC WICHITA

Form CP-2/3

JUN 21 2005

ARROW OIL OPERATIONS
 3006 NORTHRIDGE CT. #1 WALTER DECHANT 6-15-18W
 HAYS, KS 67601 C S/2 SW SE

CONTR R & C DRILLING CO. CTY ELLIS
 GEOL ALLEN DOWNING FIELD DECHANT



ELV 2013 KB SPD 8/29/84 CARD ISSUED 10/25/84 IP P 52 BO & 2.74 BWPD
 ARB OH 3599-3602

| LOG | Tops | Depth Datum |
|---------|------------|-------------|
| ANH | 1191 + 822 | |
| B/ ANH | 1235 + 778 | |
| TOP | 2988- 975 | |
| HEEB | 3248-1235 | |
| TOR | 3267-1254 | |
| LANS | 3293-1280 | |
| BKC | 3534-1521 | |
| CONG | 3572-1559 | |
| REW ARB | 3592-1579 | |
| ARB | 3597-1584 | |
| LTD | 3600-1587 | |
| RTD | 3602-1589 | |

API 15-051-23,985
 8 5/8 " 483, 5 1/2 " 3599
 DST (1) 3592-3602 (ARB) / 60-60-60-60, REC 570' CL OIL, NW,
 SIP 1020-997#, FP 35-105 / 140-210#
 MICT - CO, (ARB OH), SWB DWN, GSO, POP, P 52 BOPD & 2.74
 BWPD

DOWNING

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS