

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22451-00-00
Spot: N2SESE Sec/Twnshp/Rge: 20-18S-9W
1150 feet from S Section Line, 590 feet from E Section Line
Lease Name: SCHOONOVER FAMILY TRUS Well #: 1-20
County: RICE Total Vertical Depth: 3780 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

SURF Size: 8.625 feet: 304

#122⁸⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/23/2005 9:25 AM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN COX Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed Pumping Method: Pump 35 sxs @ top of Arbuckle; pull drill pipe to 950' and pump 35 sxs; pull to 600' and pump 35 sxs; pull to 360' and pump 35 sxs; pull to 60' and circulate 25 sxs to surface; 15 sxs in rathole; and 10 sxs in mousehole.

Plugging Proposal Received By: VIRGIL CLOTHIER
Date/Time Plugging Completed: 05/23/2005 11:40 AM

Witness Type: NONE
KCC Agent: VIRGIL CLOTHIER

RECEIVED
KCC DISTRICT #2
MAY 23 2005
WICHITA, KS

Actual Plugging Report:

Perfs:

Pumped 35 sacks of cement at Arbuckle top at 3280'. Pulled drill pipe to 950' and pumped 35 sacks of cement. Pulled drill pipe to 600' and pumped 35 sacks of cement. Pulled drill pipe to 360' and pumped 35 sacks of cement. Pulled drill pipe to 60' and circulated cement to surface. No rathole or mousehole.

60/40 posmix with 4% gel

Allied #18379

Remarks:

Plugged through: DP

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 6-10-05
AMOUNT 200506700
1700

RECEIVED

JUN 10 2005

KCC WICHITA

Form CP-2/3