

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01747-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 34-17S-8W
3087 feet from S Section Line, 5001 feet from E Section Line
Lease Name: JF ROLFS Well #: 9
County: ELLSWORTH Total Vertical Depth: 3223 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 7 feet: 3193 300 SX CMT
SURF Size: 10.75 feet: 206 200 SX CMT

#104⁷⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/27/2005 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Sand to 3143' and cap with 7 sacks of cement. Pull tubing to 1100' and pump 50 sacks of cement at perforations. Pull to
Plugging 800' and pump 50 sacks of cement at perforations. Pull to 256' and circulate to surface.
Method:

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 05/27/2005 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3140' and capped with 10 sacks of cement. Ran tubing to 1100' and pumped 50 sacks of cement. Pulled tubing to 800' and pumped 50 sacks of cement. Pulled tubing to 260' and circulated to surface with 100 sacks of cement.

Allied Cement #20670

60/40 posmix with 4% gel -- 210 sacks total

Perfs:

Top	Bot	Thru	Comments
3193	3197		
RECEIVED KCC DISTRICT #2 JUN - 1 2005 WICHITA, KS			

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED
DATE 6-10-05
VOL. NO. 2005061704

RECEIVED
JUN 10 2005
KCC WICHITA

Form CP-2/3