

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06261-00-00
Spot: N2SWNE Sec/Twnshp/Rge: 10-18S-8W
3630 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DOBRINSKI Well #: 5
County: RICE Total Vertical Depth: 3297 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

PROD Size: 5.5 feet: 3295
SURF Size: 8.625 feet: 156

\$107¹⁵

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/31/2005 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Sand perfs to 3240' and put 5 sacks of cement on top; cut off 5-1/2" casing; pull to 1150' and pump 35 sacks of cement; pull
Plugging casing to 800' and pump 35 sacks of cement; and pull casing to 250' and circulate cement to surface.
Method:

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE
Date/Time Plugging Completed: 05/31/2005 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded open hole to 3240' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 1400'.
Pulled casing to 1150' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled
casing to 800' and pumped 35 sacks of cement with 50 lbs of cotton hulls. Pulled casing to 250'
and circulated cement with 50 lbs of cotton hulls to surface.

Allied Cement #18384

60/40 posmix with 4% gel

RECEIVED
KCC DISTRICT #2
JUN - 1 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 6-10-05
INVOICE NO. 2005061705

RECEIVED
JUN 10 2005
KCC WICHITA