

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20364-00-00
Spot: W2NWNW Sec/Twnshp/Rge: 2-19S-40W
4620 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DOSKOCIL Well #: 1
County: GREELEY Total Vertical Depth: 2941 feet

Operator License No.: 3783
Op Name: BIG SKY GAS CO.
Address: PO BOX 189
TRIBUNE, KS 67879

PROD Size: 4.5 feet: 2941 WITH 600 SX CMT
SURF Size: 8.625 feet: 600 WITH 275 SX CMT

#9558

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2005 11:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: BIG SKY GAS Phone: _____

Proposed Plugging Method: PUMP 35 SX CMT & 400# HULLS, 11 BBL WATER SPACER. PUMP 95 SX CMT FROM 1600' TO 0'. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS AND ATTEMPT TO PUMP IN 90 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2005 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT & 400# HULLS. PUMP 38 SX CMT FOR CMT SPACER. PUMP 84 SX CMT FROM 1600' TO 0'. PRESSURED 4 1/2" CASING TO 400#. HELD. PUMP 3.5 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. CMT CAME OUT HOLE IN 8 5/8" CASING. 8 5/8" WAS FULL OF FLUID.


Perfs:

Top	Bot	Thru	Comments
2909	2914		
2873	2883		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Ken Jehlik
(TECHNICIAN)

INVOICED
6-10-05
2805061697

RECEIVED

JUN 10 2005

KCC WICHITA

Form CP-1/3