

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20714-00-00
Spot: SWNE Sec/Twnshp/Rge: 34-18S-40W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: CLIFT B Well #: 2-34
County: GREELEY Total Vertical Depth: 2980 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W. LOUISIANA, SUITE 200
MIDLAND, TX 79701

PROD Size: 4.5 feet: 2972 WITH 435 SX CMT
SURF Size: 8.625 feet: 304 WITH 155 SX CMT

\$96⁸⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/19/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: HAWK DEMOSS Company: HORSESHOE OPERATING Phone: (620) 376-8190

Proposed Plugging Method: PUMP 35 SX CMT & 300# HULLS. PUMP 11 BBL SPACER. PUMP 95 SX CMT FROM 1600' TO 0'. PUMP 90 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2005 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 35 SX CMT WITH 400# HULLS. PUMP 38 SX CMT FOR CMT SPACER. PUMP 95 SX CMT FROM 1600' TO 0'. PRESSURED 4 1/2" CASING TO 400#. HELD. PUMP 7 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURED TO 400# & HELD.


Perfs:

Top	Bot	Thru	Comments
2909	2914		
2884	2889		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Ken Jehlik
(TECHNICIAN)

INVOICED RECEIVED
DATE 6-10-05 JUN 10 2005
KCC WICHITA

[Handwritten signature]
Form CP-2/3