

4 060055

1-31

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-23,076 0000  
NE NE SW, SEC. 20, T 7 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

2240 feet from S section line

3090 feet from E section line

Lease Name Jones Trust Well # 1

County Rooks 112.84

Well Total Depth 3472 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address Wichita, KS

Company to plug at: Hour: 6:45AM Day: 31 Month: January Year: 19 90

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Co. (phone) 316-262-1841

were: Space all plugs through drill pipe with heavy drilling mud.

Order 215 sxs. 60/40 pos 6% gel 1/4# floccul per sx.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 6:45AM Day: 31 Month: January Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3440' with 25 sxs. Arbuckle at 3454'

2nd plug at 1510' with 25 sxs. Anhydrite 1493-1525'

3rd plug at 890' with 100 sxs. Dakota 587-887'

4th plug at 330' with 40 sxs. Surface pipe to 280'

5th plug at 40' with 40 sxs. wiper plug at 40'

rathole with 15 sxs.

Remarks: Halliburton Cementing

(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

**INVOICED**

*Handwritten initials*

Signed Herb Deines  
(TECHNICIAN)

Herb Deines

DATE 2-15-90

INV. NO. 27444