

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21392-00-00
Spot: NWNE Sec/Twnshp/Rge: 20-7S-19W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: GRIEBEL Well Number: 1
County: ROOKS Total Vertical Depth: 3497 feet

Operator License No.: 5352
Op Name: BAIRD OIL CO, INC
Address: BOX 428 MAIN STREET
LOGAN, KS 67646

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 217 150 SX CMT
Production: Size 4.5 feet: 3497 235 SX CMT
Liner: Size feet:

12/28

113.65

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/28/2000 8:00 AM

Plug Co. License No.: 5352 Plug Co. Name: BAIRD OIL CO, INC

Proposal Rcvd. from: JIM R. BAIRD Company: BAIRD OIL CO, INC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/28/2000 9:45 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set t 217' w/150 sxs cwc. 4 1/2" set at 3497' w/235 sxs.
Prod. Perfs 3326' - 3338'. PBTD at 3455'.
Shots at 1500' and 826'.
Squeezed 4 1/2" w/175 sxs cement blend with 500# hulls mixed into Max. P.S.I. 600#. Held.
Squeezed 8 5/8" w/50 sxs cement blend to Max. P.S.I. 300#. Held.
Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION
1/10/01
JAN 10 2001
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

DUPLICATED
DATE 1/10/01
NO. 2001061256

JAN 02 2001

