

MAY 13 1987 15-163.22 079.00-00

API NUMBER 15-7-9-83

6 030875

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SW, SEC. 22, T 7 S, R 19 W/E

2310 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Blaur Well # 1

Operator: Baird Oil Co., Inc.

County _____ Rooks 111.35

Name & Address: Box 428

Well Total Depth 3426 feet

Logan, Kansas 67646

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 13 Month: 5 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) 567-8645

were: 8 5/8 set at 207 4 1/2 set at 3420' with 240 sx Arb open hole with Perfs: 3234-3344

ordered 400 sx 65/35 poz 10% gel 2% Dical 10 sx hulls Allied Cement Co.

No pipe recovered hole in csg at 1100'

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4 P.M. Day: 13 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT

Mix and pump down 4 1/2 7 sx hulls 300 sx cmt mix circulated cement out annulus
closed in annulus, pumped 3 sx hulls 100 sx cmt. mix in 4 1/2 to squeeze both sides
closed in at 1000# PSI plug complete.

RECEIVED STATE CORPORATION COMMISS

JUN 4 1987 JUN 4 1987

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe the plugging

INVOICED

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

base OK 700? DATE 6-5-87

Andy 1200? INV. NO. 17159

DB