

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

RECEIVED
JUN 20 2005
KCC WICHITA

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 129-10225-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 12/07/55.

Well Operator: WESTPORT OIL & GAS COMPANY, LP KCC License #: 33002
(Owner / Company Name) (Operator's)

Address: 5735 PINELAND, SUITE 300 City: DALLAS

State: TEXAS Zip Code: 75231 Contact Phone: (214) 692 - 1800

Lease: HAYWOOD NATIONAL UNIT Well #: 1 Sec. 04 Twp. 35 S. R. 42 East West

C - SE Spot Location / QQQQ County: MORTON

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 1388' Cemented with: 750 Sacks

Production Casing Size: 5-1/2" Set at: 3035' Cemented with: 350 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2934'-70' - RBP @2927'; 2912'-18', 2898'-2900', 2811'-13', 2772'-74' - CIBP @ 2737'; 2719'-28', 2708'-11', 2681'-85', 2484'-89' - OPEN

Elevation: 3571' (G.L. / K.B.) T.D.: 4815' PBDT: 2737' Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SET CIBP@2700'W/2 SXS.CMT.;CIRC.WELL W/PXA MUD; CUT&PULL 5-1/2"CSG.@1440'; PUMP 50 SX. CMT. PLUP@1440'-1335' - WOC & TAG; PUMP 40 SX.CMT.PLUG@750'-650'; SPOT 5 SX.CMT.SURF.PLUG @ 13'-3'; DIG OUT & CUT OFF WELLHEAD 3' B.G.L.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DAVID A. EYLER
Phone: (432) 687 - 3033

Address: 223 W. WALL AVE., SUITE 707 City / State: MIDLAND, TEXAS 79701

Plugging Contractor: SARGENT & HORTON PLUGGING, INC. KCC License #: 31151

Address: RR 1, BOX 49BA, TYRONE, OK 73951 Phone: (580) 854 - 6515

Proposed Date and Hour of Plugging (if known?): ESTIMATED 05/01/05 5-6-05 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 05/05/05 Authorized Operator / Agent: David A. Eyer
(Signature)

3/04

Yob