

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-173-01327-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 6-12-63.

Well Operator: VAL Energy Inc. KCC License #: 5822  
(Owner / Company Name) (Operator's)

Address: Box 116 City: Wichita  
State: Kansas Zip Code: 67201 Contact Phone: (316) 263-6688

Lease: Betzen Well #: 2 Sec. 24 Twp. 27 S. R. 2  East  West  
S/2 - S/2 - SW - Spot Location / QQQQ County: Sedgwick

330 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)  
1160 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # C-21,741  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8 Set at: 412 Cemented with: 275 Sacks  
Production Casing Size: 5 1/2 Set at: 3520 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4 1/2" liner set from 3437 to 3804, 5 1/2 CIBP @ 3434, 5 1/2 CIBP @ 3398, Miss perms @ 3420 to 3428 squeezed off with cement

Elevation: 1328 ( G.L. /  K.B.) T.D.: 3891 PBDT: 3826 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): All perms squeezed off, set 5 1/2 CIBP @ 3434 to shut off Liner, Set 5 1/2 CIBP @ 3398 & top w/2 sx cement, perms @ 500', run tubing and circulate cement to surface inside and out, No casing pulled, Verbal OK to plug by Doug Lewis & Dave Wertz on 6-9-05

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 21 2005

CONSERVATION DIVISION  
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Todd Allam

Phone: (316) 263-6688

Address: Box 116 City / State: Wichita, Ks. 67201

Plugging Contractor: Sams Well Service KCC License #: 31539  
(Company Name) (Contractor's)

Address: Arkansas City, Ks. Phone: (620) 441-3943

Proposed Date and Hour of Plugging (if known?): 6-13-05 10:00 A.M. Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: 6-10-05 Authorized Operator / Agent: Todd Allam  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202