

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

JUN 20 2005

Form CP-1
September 2003

This Form must be Typed
All blanks must be Filled

WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

KCC WICHITA

API # 15 - 191-00493-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 1948.

Well Operator: AGV Corp. KCC License #: 5039
(Owner / Company Name) (Operator's)

Address: 123 N. Main City: Attica

State: Kansas Zip Code: 67009 Contact Phone: (620) 254 - 7222

Lease: Watkins "A" Well #: 1 Sec. 32 Twp. 32 S. R. 4 East West

- NE - NE - SE Spot Location / QQQQ County: Sumner

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: N/A Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 3/4" Previously Set at: 178' Cemented with: N/A Sacks

Production Casing Size: 5 1/2" Set at: 3395' w/ Port Collar @ 321' Cemented with: 300 sx on bottom / 200 sx from 321' to surface Sacks

List (ALL) Perforations and Bridgeplug Sets: Pf: 3252'-62'. CIBP @ 3245'. Pf: 3216'-22'. CIBP @ 3200'. Pf: 2570'-76'. CIBP @ 2554'. Pf: 2484'-90'. CIBP @ 2382'. Pf: 2292'-96'

Elevation: 1263 (G.L. / K.B.) T.D.: 3415' PBDT: 3367' Anhydrite Depth: N/A
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per Butch Hoberecht (District #2). Sand back from 2382' to 2240' & cap w/ 2 sx cement. Run tubing and Circulate cement from 600' to surface.

Port collar was cemented from 321' to surface on 9/17/03 w/ 200 sx. (Circulated 20 sx to pit)

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Kent Roberts

Phone: (316) 215 - 1683

Address: 520 S. Holland, Suite 207. City / State: Wichita, Ks 67209

Plugging Contractor: Shawnee Well Service KCC License #: 30346
(Company Name) (Contractor's)

Address: P.O. Box 333, Attica Kansas 67009 Phone: (620) 254 - 7893

Proposed Date and Hour of Plugging (if known?): As soon as rig scheduling permits

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/17/05 Authorized Operator / Agent: Kent Roberts / Agent
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

4/04

3/04

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

AGV Corp.
123 N. Main
Attica, KS 67009

June 27, 2005

Re: WATKINS #A1
API 15-191-00493-00-01
NENESE 32-32S-4W, 2310 FSL 330 FEL
SUMNER COUNTY, KANSAS

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely


David P. Williams
Production Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000