

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990
6/26/90
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,574-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR K & E Drilling, Inc. OPERATOR'S LICENSE NO. 5266

ADDRESS 100 S. Main, #300, Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Hamel WELL NO. 3 WELL LOCATION W/2 SE NW SE COUNTY Graham

SEC. 13 TWP. 7S RGE. 21 (~~S~~) or (W) TOTAL DEPTH 3580 PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 218 CEMENTED WITH 160 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill hole w/heavy mud to 3515: 1st plug at 3515 w/25 sx

2nd plug at 1700 w/25 sx, 3rd plug at 920' w/100 sx, 4th plug at 220' w/40 sx, 5th plug

solid bridge at 40' w/10 sx, 15 sx in rathole.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? No

(If not explain.) Sent to operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:00 a.m. on 6-19-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # () _____

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

Jack K. Wharton
(Operator or Agent)

DATE:

June 25, 1990

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

K & E Drilling, Inc.
100 S. Main, Suite 300
Wichita, KS 67202

Hamel #3
W/2 SE NW SE
Sec. 13-7S-21W
Graham County, Kansas

CONTRACTOR: Abercrombie Drilling, Inc.

8 5/8 at 218 w/160 sx

DRILLER'S WELL LOG

06-14-90	0 - 220	Clay, Sand & Shale
06-15-90	220 - 242	Sand & Shale
	242 - 1685	Shale & Sand
	1685 - 1716	Anhydrite
	1716 - 1957	Shale & Sand
06-16-90	1957 - 2137	Sand & Shale
	2137 - 2756	Shale
06-17-90	2756 - 3195	Shale & Lime
	3195 - 3295	Lime
06-18-90	3295 - 3405	Shale & Lime
	3405 - 3515	Lime
06-19-90	3515 - 3580	Shale & Lime
	3580	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990

CONSERVATION DIVISION
Wichita, Kansas

6/26/90