

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-065-22,382-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR K & E Petroleum, Inc. OPERATORS LICENSE NO. 5267

ADDRESS 300 Hardage Center, 100 S. Main, Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Hamel WELL NO. 2 WELL LOCATION 150' N of E/2 SW COUNTY Graham

SEC. 13 TWP. 7S RGE. 21 ~~EXOR~~ (W) TOTAL DEPTH 3610 PLUG BACK TO

Check One:

OIL WELL  GAS WELL  D & A X SWD or INJ WELL  DOCKET NO.

SURFACE CASING SIZE 8-5/8 SET AT 227 CEMENTED WITH 180 SACKS

CASING SIZE  SET AT  CEMENTED WITH  SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR  CASING LEAK  JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 3530'-25 sacks; 2nd plug @ 1700'-25 sacks;  
3rd plug @ 920'-100 sacks and 1 sack celoflake; 4th plug @ 270'-40 sacks; 5th plug @ 40' to solid bridge with  
wiper plug-10 sacks; rathole-15 sacks; all cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACC-1 FILED? no  
(If not, explain) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 2:45 p.m. 8-23-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley

PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Abercrombie Drilling, Inc.

LICENSE NO. 5422

AUG 26 1987

ADDRESS 801 Union Center, Wichita, KS 67202

PHONE # (316) 262-1841

8-26-87

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Jack K. Wharton  
(Operator or Agent)

Jack K. Wharton, Secy/Treas

DATE: 8-25-87