

15-065-20852-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 14 Twp. 7 Rge. XIV 22 (W)
Location as "NE/CNWxSWx" or footage from lines SE-SW-SW
Lease Owner A. D. Worcester
Lease Name A. D. Worcester Well No. B-1
Office Address ~~318 EXXESS~~ Hill City, Kansas 67642
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 8-21 19 76
Application for plugging filed 8-23 19 76
Application for plugging approved (oral) 19 76
Plugging commenced 8-21 19 76
Plugging completed 8-21 19 76
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Baltizor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3660 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	168	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 800' with 70 sacks of 50-50 Pozmix cement 6% gel. Second plug at 150' with 20 sacks 50-50 poz. Built bridge in surface pipe at 40' and fill to surface with 10 sacks. Hole filled with drilling mud between each plug. Used Halliburton pump truck and cement and plugged through open end drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1976

CONSERVATION DIVISION
Wichita, Kansas

8/31/76


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Address Hays, Kansas

STATE OF Kansas, COUNTY OF Graham, ss.
A. D. Worcester (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
318 E. Cedar Hill City, Kansas 67642
(Address)

Subscribed and sworn to before me this 23 day of August, 19 76
My commission expires Dec. 26, 1976



[Signature]
Notary Public.

15-065-20852-00-00

DRILLERS LOG

WORCESTER #B-1

CASING RECORD:

8 5/8" set at 168'

TOTAL DEPTH:

3660'

OPERATOR:

A. D. Worcester

CONTRACTOR:

Helberg Oil Company

COMMENCED:

August 13, 1976

COMPLETED:

August 21, 1976

DESCRIPTION:

SE SW SW
Sec. 14-7-22, Graham County, Kansas

FORMATION	FROM	TO	REMARKS
Shale	0	183	
Shale	183	900	
Shale	900	1350	
Sand	1350	1550	
Shale & Shells	1550	1568	
Sand & Shale	1568	1836	
Shale	1836	2108	
Shale	2108	2350	
Lime & Shale	2350	2460	
Lime & Shale	2460	2561	
Lime & Shale	2561	2720	
Lime & Shale	2720	2860	
Lime & Shale	2860	2938	
Lime & Shale	2938	3045	
Lime & Shale	3045	3148	
Lime & Shale	3148	3249	
Lime & Shale	3249	3360	
Lime & Shale	3360	3444	
Lime & Shale	3444	3501	
Lime & Shale	3501	3569	
Lime	3569	3634	
Lime	3634	3660	
T.D.	3660		

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1976

CONSERVATION DIVISION
Wichita, Kansas

8/31/76

I certify that this is a true and correct copy of the above log to the best of my knowledge.

HELBERG OIL COMPANY

Jerry M. Helberg
Jerry M. Helberg

Subscribed and sworn to before me this 30th day of August, 1976.

Faye E. Minium
Faye E. Minium, Notary Public

