


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 14 Twp. 7S Rge. 22 (E) (WX)
Location as "NE/CNW/SW" or footage from lines SW NE SW
Lease Owner A.D. Worcester
Lease Name Worcester "B" Well No. #2
Office Address R.R. Hill City, Kansas 67642
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-13 19 81
Application for plugging filed 12-13 19 81
Application for plugging approved 12-13 19 81
Plugging commenced 12-13 19 81
Plugging completed 12-13 19 81
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	202'	8 5/8"	202'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. Plug set at 980' with 70 sacks common cement 3%Cal Cl 6%Gel 50-50poz
2nd. Plug set at 210' with 40 sacks common cement 3%Cal Cl 6%Gel 50-50poz
3rd. Plug set at 40' with 10 sacks common cement 3%Cal Cl 6%Gel 50-50poz
10 sacks in rathole
Heavy drilling mud between each plug


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing
Address Hays, Kansas 67601

STATE OF Kansas, COUNTY OF Graham, ss.
Jerry M. Helberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry M. Helberg
Box 32 Morland, Kansas 67650
(Address)

Subscribed and sworn to before me this 16 day of December, 1981
My commission expires 12-4-83



RECEIVED
STATE CORPORATION COMMISSION
Notary Public.
DEC 17 1981

CONSERVATION DIVISION
Wichita, Kansas

12/17/81

DRILLERS LOG

WORCESTER "B" #2

CASING RECORD:

8 5/8" set at 202'

TOTAL DEPTH:

3775'

DESCRIPTION:

SW NE SW

Sec. 14, Twp. 7, Rge. 22.

OPERATOR: A.D. Worcester

CONTRACTOR: Helberg Oil Company

COMMENCED: December 4, 1981

COMPLETED: December 13, 1981

FORMATION	FROM	TO	REMARKS
Shale	0	225	
Shale	225,	785	
Shale	785	1440	
Sand & Shale	1440	1818	
Anhydrite	1818	1850	
Shale	1850	1964	
Shale	1964	2153	
Shale	2153	2290	
Shale	2290	2389	
Shale & Lime	2389	2527	
Shale & Lime	2527	2640	
Shale & Lime	2640	2816	
Shale & Lime	2816	2924	
Shale & Lime	2924	3005	
Lime & Shale	3005	3135	
Lime & Shale	3135	3240	
Lime & Shale	3240	3320	
Lime & Shale	3320	3409	
Lime & Shale	3409	3471	
Lime & Shale	3471	3537	
Lime & Shale	3537	3600	
Lime & Shale	3600	3655	
Lime	3655	3720	
Lime	3720	3760	
Lime	3760	3775	
T.D.		3775	D&A

I certify that the above is a true and correct copy of the log to the best of my knowledge.

Helberg Oil Company

Jerry M. Helberg

 Jerry M. Helberg

Subscribed and sworn to before me this 16 day of December, 1981

Janice Rechner

 Notary Public



My commission expires 12-4-83

RECEIVED
 STATE CORPORATION COMMISSION

DEC 17 1981

CONSERVATION DIVISION
 Wichita, Kansas

12/17/81