

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-22,574-00-00

LEASE NAME Hamel

WELL NUMBER 3

1650 Ft. from S Section Line

1815 Ft. from E Section Line

SEC. 13 TWP. 7S RGE. 21 (X) or (W)

COUNTY Graham

Date Well Completed 6-19-90

Plugging Commenced 6-19-90

Plugging Completed 6-19-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR K & E Drilling, Inc.

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202

PHONE# (316) 264-4301 OPERATORS LICENSE NO. 5266

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-19-90 (date)

by Gilbert Balthazar (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 218 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

JUN 26 1990
 6/26/90
 CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Filled hole w/heavy mud: 1st plug at 3515 to 3415 w/25 sx; 2nd plug at 1700 to 1600 w/25 sx; 3rd plug at 920' to 520' w/100 sx; 4th plug at 220 to 60' w/40 sx; 5th plug solid bridge from 40' to surface w/10 sx; 15 sx in rathole. All cement 60/40 pozmix, 6% gel, 3% cc, 1/4# Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: K & E Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
 Wichita, KS 67202



AND SWORN TO before me this 25th day of June, 19 90

Susan M. Williams
 Notary Public

My Commission Expires: 8/15/92