

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,316 60-00

LEASE NAME Warren

WELL NUMBER 2

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 12 TWP. 7 RGE. 21 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 4-17-92

Plugging Completed 4-17-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well oil SWD *KCC ap 6-28-05*

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-17-92 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation LKC Depth to Top 3324 Bottom 3592 T.D. 3696

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	225	0
				5 1/2	3618	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 50 sxs 65/35 pozmix & 10% gel down tubing. Pumped 100 sxs 65/35 pozmix & 10% gel with 300# hulls down tbq. Pulled tbq up to 1250'. Pumped 100 sxs 65/35 pozmix & 10% gel w/ 200# hulls down tbq. Cement circulated to surface. Pulled the out of hole. Loaded csg w/25 sxs 65/35 pozmix, 10% Gel. Pressured up. Cmt @ (If additional description is necessary, use BACK of this form.) surface.

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 125 N. Market, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1992

[Signature]
Notary Public



Commission Expires: 8-29-95

RECEIVED
MAY 7 1992
CORPORATION COMMISSION
Wichita, Kansas
Form CP-4
Revised 05-88

5/7/92