

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,382 - 00-00

LEASE NAME Hamel

WELL NUMBER 2

810 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 13 TWP. 7 RGE. 21 ~~XXXX~~ (W)

COUNTY Graham

Date Well Completed 8-23-87

Plugging Commenced 8-23-87

Plugging Completed 8-23-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR K & E Petroleum, Inc.

ADDRESS 300 Hardage Center, 100 S. Main, Wichita, KS 67202

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5267

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? no If not, is well log attached? no

Sent to operator for completion
Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	227	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump heavy mud to 3530'-3430', 25 sacks; pump heavy mud to 1700'-1600', 25 sacks; pump heavy mud to 920'-520', 100 sacks and 1 sack celoflake; pump heavy mud to 270'-110', 40 sacks; pump heavy mud to 40' to solid bridge with wiper plug-10 sacks; rathole-15 sacks; all cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422


Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Secy/Treas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 87

Clarice M. Mize
Clarice M. Mize Notary Public

Commission Expires: November 28, 1988

AUG 26 1987
8120/87
Form CP-4
Conservation Division
Wichita, Kansas
Revised 07-86