

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-065-22,367-20-LSU

LEASE NAME Brin

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 13 TWP. 7S RGE. 21 (XXX) (W)

COUNTY Graham

Date Well Completed 05-03-87

Plugging Commenced 05-03-87

Plugging Completed 05-03-87

LEASE OPERATOR K & E Petroleum, Inc.

ADDRESS 100 S. Main, #300, Wichita, KS 67202

PHONE#(316) 264-4301 OPERATORS LICENSE NO. 5267

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? no If not, is well log attached? no

Sent to operator for completion

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	243	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump heavy mud to 3575'-3475', 25 sx; pump heavy mud to 1715'-1615', 25 sx; pump heavy mud to 935'-535', 100 sx and 1 sx flocel; pump heavy mud to 290'-130', 40 sx; pump heavy mud to 40' with wiper plug; rathole-10 sx; all cement 60/40 posmix, 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422


Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Secretary/Treasurer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton  
 Jack K. Wharton  
 (Address) 801 Union Center, Wichita, KS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 5/8/87  
 MAY 8 1987  
 CONSERVATION DIVISION  
 Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 87

Clarice M. Mize  
 Clarice M. Mize Notary Public

Commission Expires: November 28, 1988