

15-065-01020-00 ~~025-065-00077-00-00~~


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

Graham County. Sec. 12 Twp. 7 Rge. 21 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE NE SW/4
Lease Owner Veeder Supply & Development Co.
Lease Name Hibbits Well No. 2
Office Address Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. April 16-48 19
Application for plugging filed. " 16-48 19
Application for plugging approved. " 16-48 19
Plugging commenced. " 16-48 19
Plugging completed. " 16-48 19
Reason for abandonment of well or producing formation. Dry Hole
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr Rize, Hays, Kansas
Producing formation. Depth to top. Bottom. Total Depth of Well 3701 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled with Mud 205 to 3701' set Bridge plug @205' Ran 15 sacks cement
170' to 205' filled with mud from 170' to 15', Placed wood bridge plug @
15' placed 10 sacks cement on top of plug filling with cement to surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Veeder Supply & Development Co.
Address P.O. Box 201 Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Gordon T. Adams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Gordon T. Adams
Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21st day of May, 1948.
Leo L. Veeder
Notary Public.

My commission expires 10-14-48


PLUGGING
FILE SEC 12 T 7 R 21
BOOK PAGE 23 LINE 45

2-48-15M

5-24-48

~~15-065-0077-00-00~~
15-065-01020-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for National Cooperative Refinery Ass'n. Farm Hibbitts No. 2 Depth 3700'
And Veeder Supply & Dev. Co.
 Contractor Veeder Supply & Development Co. Pipe 200' of 8 5/8" Surface casing - Cemented with
105' casing
 Location NE NE SW Sec. 12 Twp. 7 Range 21N
 Commenced April 2, 1948 Completed April 16, 1948 County Graham State Kansas

FORMATION LOG

Surface Soil	0	70	70	
Sand, shale	70	190	120	
Shale	190	205	15	
Cemented 116-205				<u>Topset - Rig Floor</u>
Shale	205	585	380	Lansing K. O.
Sand, shale	585	624	39	Conglomerate
Shale	624	1020	406	Weathered
Sand, shale	1020	1150	130	Arbuckle
Sand	1150	1200	50	Solid Arbuckle
Sand, shale	1200	1250	50	
Shale, shells	1250	1500	250	
Redbed, shale	1500	1570	70	
Redbed	1570	1600	30	
Shale, shells	1600	1730	130	
Anhydrite	1730	1780	50	
Shale, shells	1780	2080	300	
Shale, lime shells	2080	2185	105	
Shells, shale	2185	2310	125	
Shale, shells	2310	2475	165	
Lime, shale	2475	2600	125	
Shale, limeshells	2600	2710	110	
Lime & shale	2710	2905	195	
Shale, shells	2905	3100	195	
Lime, shale	3100	3140	40	
Shale, lime	3140	3185	45	
Lime, shale	3185	3280	95	
Lime	3280	3310	30	
Lime, shale	3310	3372	62	
Lime	3372	3580	208	
Lime, shale	3580	3625	45	
Conglomerate	3625	3634	9	
Arbuckle	3634	3640	6	
Lime	3640	3659	19	
Arbuckle	3659	3700	41	

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF MONTGOMERY) ss:

HERBERT C. VEEDER, of lawful age, being duly and solemnly sworn on oath says:
 I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and
 on oath state, that the above drilling log covering the Hibbitts #2 well in Section 12
 7-21N, Graham County, Kansas is true and correct.
 Further affidavit saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY,
 By: _____

Subscribed and sworn to before me this 20th day of April, 1948.



Notary Public

My Commission Expires: July 11, 1948

PLUGGING
 FILE 23 15
 BOOK 15