


15-065-00482-00-00

STATE OF KANSAS
STATE-CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 12 Twp. 7S Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines 100' So. of SW SW SW
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Neu Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 3 19 58
Application for plugging filed September 3 19 58
Application for plugging approved September 3 19 58
Plugging commenced September 3 19 58
Plugging completed September 3 19 58
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	8-22-58	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 plug at 550' with 25 sacks cement; Set No. 2 plug at 180' with 15 sacks cement. Set No. 3 plug at 40' with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~Imperial Oil of Kansas, Inc.~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P.
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September 19 58

My commission expires July 7, 1962
Mona L. Latier Notary Public.

PLUGGING
FILE SEC 12 T 7 R 21W
BOOK PAGE 130 LINE 9

9/15/58

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Neu No. 1
100' So. of SW SW SW Sec. 12-7S-21W
Graham County, Kansas

Total Depth: 3705'

Elevation: 2156' RB
Production: D & A

Commenced: 8-22-58 Completed: 9-3-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 184' with 150 sacks cement.

Figures indicate bottom of formations:

TOPS

Surface Sand & Clay	184'		
Shale & Sand	1295'	Anhydrite	1756' (/ 400)
Dakota Sand	1500'	Heebner	3346' (-1193)
Shale & Shells	1756'	Toronto	3370' (-1217)
Anhydrite	1788'	Lansing	3385' (-1232)
Red Bed & Shale	1855'	Weathered Pre-Cambrian	3648' (-1495)
Shale & Shells	2460'	Rotary Total Depth	3705' (-1552)
Shale & Lime	3285'		
Lime	3625'		
Lime & Sand	3637'		
Lime	3705'		
Total Depth	3705'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon
Vice-President

Subscribed and sworn to before me this 10th day of September, 1958.

My Commission Expires:

July 7, 1962

Mona L. Latier
Notary Public

PLUGGING			
FILE	SEC	T	R
	12	7	21W
BOOK	PAGE	LINE	
	130	9	