

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Tarkio Depth to Top: 2458 Bottom: 2467 T.D. \_\_\_\_\_  
Toronto & LKC Depth to Top: 2909 Bottom: 3123 T.D. \_\_\_\_\_  
Arbuckle OH Depth to Top: 3254 Bottom: 3283 T.D. 3283

API Number: 15-167-01790-000  
Lease Name: Sutton-Mai  
Well Number: #2  
Spot Location (QQQQ): \_\_\_\_\_ - S/2 - SW - SE  
\_\_\_\_\_ Feet from  North /  South Section Line  
\_\_\_\_\_ Feet from  East /  West Section Line  
Sec. 5 Twp. 12S S. R. 15W  East  West  
County: Russell  
Date Well Completed: January 1964  
Plugging Commenced: 5/18/05  
Plugging Completed: 5/18/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	869	425
				5-1/2	3254'	150
CIBP's - 3066' & 3170'						

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1500' and 850'. TIH w/tbg to 2800'. Pumped down tubing with 100 sx 60/40 poz w/10% gel and 500# hulls.  
Pulled tbg to 1400' and pumped another 100 sx same cement with 100# hulls. Pld tbg to 800' and pumped another 75 sx same cement and circulated to surface. Connected to 5 1/2" csg and pumped 35 sx same cement. Press to 500#  
Connected to 8 5/8" and 5 1/2" annulus and pumped 40 sx same cement. Press to 400#. Approved by KCC.


Name of Plugging Contractor: Allied Cementing Co., Inc. Smokey Hills Well Service License #: 32452  
Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss. \_\_\_\_\_  
Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 7th day of June  
Michelle D. Henning My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN - 9 2005  
KCC WICHITA

[Handwritten initials]

# ALLIED CEMENTING CO., INC.

16570

Federal Tax I.D.# ~~000000000~~

TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>5-19-05</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>9:00am</u>	JOB FINISH <u>11:00am</u>
LEASE <u>3000 Mo</u>	WELL # <u>2</u>	LOCATION <u>Garham 1E 9N Winto</u>		COUNTY <u>Russell</u>	STATE <u>Ks</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Smoky Hills Well Service

TYPE OF JOB Old Hole Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT

AMOUNT ORDERED 350 sks 60/40 1086cl

6 Hulls

COMMON	<u>210 sks</u>	@	<u>8.70</u>	<u>1827.00</u>
POZMIX	<u>140 sks</u>	@	<u>4.70</u>	<u>658.00</u>
GEL	<u>30 sks</u>	@	<u>14.00</u>	<u>420.00</u>
CHLORIDE		@		
ASC		@		
<u>600# Hulls</u>		@	<u>21.00</u>	<u>126.00</u>
HANDLING	<u>386</u>	@	<u>1.60</u>	<u>617.60</u>
MILEAGE	<u>.06 x 386 / mile</u>		<u>17</u>	<u>393.72</u>
TOTAL				<u>4042.32</u>

EQUIPMENT

PUMP TRUCK CEMENTER Steve Bill

# 345 HELPER Craig

BULK TRUCK

# 362 DRIVER Keith

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

REMARKS:

Mix 100 sks 5 Hulls @ 2800

Mix 100 sks @ 1400

Mix 75 sks 1 Hulls @ 700 (isculated)

Mix 35 sks down casing pressure to 500 psi & shut in

Mix 40 sks backside pressure to 400 psi shut in

CHARGE TO: Voss

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 100.00

EXTRA FOOTAGE \_\_\_\_\_ @ \_\_\_\_\_

MILEAGE 17 @ 5.00 85.00

TOTAL 685.00

PLUG & FLOAT EQUIPMENT

MANIFOLD \_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

\_\_\_\_\_ @ \_\_\_\_\_

TOTAL 685.00

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE \_\_\_\_\_



RECEIVED

PRINTED NAME \_\_\_\_\_

JUN - 9 2005

KCC WICHITA

PRINTED NAME \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.