

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
Phone: (316) 682-1537 Operator License #: 5030
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8/4/04 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2554 Bottom: 2772 T.D. 2710
LKC Depth to Top: 2836 Bottom: 2996 T.D. _____
Arbuckle Depth to Top: 3138 Bottom: 3142 T.D. 3280

API Number: 15 - ~~159~~.167.01789-0805
Lease Name: Sutton-Mai
Well Number: #1
Spot Location (QQQQ): _____ - NW - SW - SE
990' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 5 Twp. 12S S. R. 15W East West
County: Russell
Date Well Completed: 5/12/59
Plugging Commenced: 5/16/05
Plugging Completed: 5/16/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	753'	335
				5-1/2	3190'	125
CIBP's - 2710'; 2825';	3076'; 3175'					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

MIRU to P&A. Plugged as follows: TIH w/tbg to 2600'. Spotted 50 sx 60/40 poz w/10% gel w/200# hulls.
Spotted w/13 sx gel. Pulled tbg to 1400'. Circulated cement to surface with 115 sx same cement.
Connected to 8 5/8" and 5 1/2" annulus and pressured to 200#. Connected to 5 1/2" casing and
pumped 35 sx same cement. SIP - 200#. Approved by KCC.


Name of Plugging Contractor: Allied Cementing Co., Inc. Smokey Hills Well Service License #: 32452
Address: P.O. Box 31, Russell, KS 67665-0031
Name of Party Responsible for Plugging Fees: Vess Oil Corporation
State of Kansas County, Sedgwick, ss.

RECEIVED
JUN - 9 2005
KCC WICHITA

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 7th day of June
Michelle D. Henning My Commission Expires _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm

ALLIED CEMENTING CO., INC.

Federal Tax I.D.# ~~000000000~~

PO BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>5/16/05</u>	SEC.	TWP.	RANGE	CALLED OUT <u>7:00 a.m.</u>	ON LOCATION <u>8:45 am</u>	JOB START <u>9:00 am</u>	JOB FINISH <u>11:30 p.m.</u>
LEASE <u>Sutton #1</u>			WELL# <u>1</u>	LOCATION <u>1 E Gorham 10 n w into</u>		COUNTY <u>Russell</u>	STATE <u>Ks</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Smoky Hill Well Service OWNER _____

TYPE OF JOB Old Hole Plug

HOLE SIZE	T.D.
CASING SIZE <u>5 1/2</u>	DEPTH <u>3190'</u>
TUBING SIZE <u>2 3/4</u>	DEPTH <u>2600</u>
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <u>300 psi.</u>	MINIMUM <u>200 psi.</u>
MEAS. LINE	SHOE JOINT

CEMENT

AMOUNT ORDERED 200 60/40 10% Gel
15 gal on site 300 # Hulls

CEMENT LEFT IN CSG. _____
PERFS. _____
DISPLACEMENT _____

COMMON	<u>120 sk</u>	@	<u>8.70</u>	<u>\$1044.00</u>
POZMIX	<u>80 sk</u>	@	<u>4.70</u>	<u>\$376.00</u>
GEL	<u>30 sk</u>	@	<u>14.00</u>	<u>\$420.00</u>
CHLORIDE		@		
ASC		@		
Hulls	<u>3 sks</u>	@	<u>21.00</u>	<u>63.00</u>
HANDLING	<u>230s</u>	@	<u>1.60</u>	<u>368.00</u>
MILEAGE	<u>17</u>	@	<u>.06</u>	<u>234.00</u>
TOTAL				<u>2505.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Shane</u>
# <u>366</u>	HELPER <u>Alan</u>
BULK TRUCK	
# <u>213</u>	DRIVER <u>Keith</u>
BULK TRUCK	
#	DRIVER <u>Fred</u>

REMARKS:

Mixed 13 gal @ 2600' + 50 sks
with 3000 # Hulls pulled up to
1400' circulate cement took mixed
100 sks on pulled up to 820'
Circulate cement with 15 sks
came out put snags on mixed 35 sks
plug shut in with 200 psi. backside
held 200 psi

SERVICE


DEPTH OF JOB				
PUMP TRUCK CHARGE			<u>750.00</u>	
EXTRA FOOTAGE	@			
MILEAGE	@	<u>5.00</u>	<u>85.00</u>	
TOTAL				<u>835.00</u>

CHARGE TO: Vess Oil
STREET _____
CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

MANIFOLD	@			
	@			
	@			
	@			
	@			
TOTAL				

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

Thank you

SIGNATURE _____

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME

RECEIVED
JUN - 9 2005
KCC WICHITA