

STATE OF KANSAS
STATE CORPORATION
COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-007-20703 - 00 - 00 ⁰⁷⁷

LEASE NAME Robinson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER G-1

1650 Ft. from N (S) Section Line

1980 Ft. from (E) W Section Line

LEASE OPERATOR Woolsey Petroleum Company

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202

PHONE # 620-886-5606 OPERATOR'S LICENSE NO. 33168

Character of Well good

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/25/2005 (date)

by Doug Lewis (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 3634 Bottom 3644 T. D. CIBP @3663

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	267	None
				4 1/2	3899	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Set CIBP at 3575', (5/9/05) dump 3 sacks portland cement with dump bailer, stretch and cut pipe at 2900, (5/10/05) cut pipe at 2800' and pull pipe, run tubing to 1250', load hole, Allied pump 35 sacks, pull to 800', pump 35 sacks, pull to 325', 125 sacks to surface, 60/40 poz, 4% jel

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Company

STATE OF Kansas COUNTY of Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 9 day of June, 2005

Glenda Morrison
Notary Public

My Commission Expires: November 30, 2006

RECEIVED
JUN 10 2005
KCC WICHITA *bw*