

15-065-01303-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER compl 4/59

LEASE NAME Mildrexter "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

SPOT LOCATION C NW NE

SEC. 6 TWP. 7S RGE. 22W (E) or (W)

COUNTY Graham

Date Well Completed 4/11/59

Plugging Commenced 5/22/87

Plugging Completed 5/23/87

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE # () 267-3241 OPERATORS LICENSE NO. 6033

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays

Is ACO-1 filled? no If not, is well log attached? yes

Producing formation LKC/ARB Depth to top 3790' bottom 4145' T.D. 4145'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	209'	--
				5 1/2"	4045'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Perf 1987 1/2-88 1/2' & 1275-76' w/4 SPF. Hooked up to 5 1/2" csg., mixed total of 400 sx. Econolite w/6 sx hulls. Cmt circ. out 8 5/8" & 5 1/2" annulus w/82 bbls. pumped. SI braden head. Pumped remainder cmt, 243 bbls. cmt. total. Max press 300 psig, SIP 100 psig. Approved by Carl Goodrow w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address 250 N. Water, Suite 300; Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Larry M. Jack, Eastern Div., Prod. Mgr.

(employee of operator) or

(operator) of above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: Larry M. Jack

(Address) Wichita, KS

JUN 26 1987
06-26-87
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 25 day of June, 1987

KERRAN REDINGTON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2-6-90

Kerran Redington
Notary Public
Kerran Redington

My Commission expires: 2/6/90

