

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.
Address: PO Box 47, Great Bend, KS 67530
Phone: (620) 793-5100 Operator License #: 6569
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6/9/05 (Date)
by: Roger Moses (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3953 Bottom: 3991 T.D. 3991

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-01388-00-00
Lease Name: Ogallah Unit
Well Number: 11-4
Spot Location (QQQQ): NE-SW-NW
3630 Feet from North / South Section Line
4290 Feet from East / West Section Line
Sec. 36 Twp. 12 S. R. 22 East West
County: Trego
Date Well Completed: Jan 1952
Plugging Commenced: 6/9/05
Plugging Completed: 6/9/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	523	8 5/8"	Jan 1952	
		0	3953	5 1/2"	Jan 1952	


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

See attached report
~300 sks thru tubing at 2200' and 1100' + from surface

Name of Plugging Contractor: DS&W Well Servicing License #: 6901
Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.
State of Kansas County, Barton, ss.

Jacob Porter (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob H Porter
(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 21st day of June, 20 05
Elaine Schreck My Commission Expires: 12-13-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
JUN 22 2005
KCC WICHITA

CARMEN SCHMITT INC
OGALLAH UNIT 11-4
PLUGGING

06-09-05

M.I.R.U. D. S. & W. WELL SERVICE. L-K WIRELINE PERF 920 FT AND 1750 FT. RAN TUBING TO 2200 FT. ALLIED CEMENTING MIXED 100 SKS OF 60-40 POZ AND 10% GEL, WITH 200 HULLS. PUMPED DOWN TUBING. PULLED TUBING TO 1100 FT., MIXED 100 SKS AND 200 HULLS, CIRCULATED TO SURFACE. LAID TUBING OUT AND TIED ON TO SURFACE PIPE. MIXED 15 SKS AND PRESSURED TO 500 P.S.I. TIED BACK ON 5-1/2, MIXED 115 SKS AND 200 HULLS DOWN CASING AT 500 P.S.I. SHUT IN AT 400 P.S.I. ROGER MOSES WITNESSED JOB

RECEIVED
JUN 22 2005
KCC WICHITA