

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.  
Address: PO Box 47, Great Bend, KS 67530  
Phone: (620) 793-5100 Operator License #: 6569  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6/8/05 (Date)  
by: Roger Moses (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 4017 Bottom: 4033 T.D. 4033  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-00816-00-00  
Lease Name: Ogallah Unit  
Well Number: 7-7  
Spot Location (QQQQ): - NW- NW- SW  
2310 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 25 Twp. 12 S. R. 22  East  West  
County: Trego  
Date Well Completed: May 1964  
Plugging Commenced: 6/8/05  
Plugging Completed: 6/8/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	328	8 5/8"	May 1964	
		0	4017	5 1/2"	May 1964	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


See attached report  
~ 225 sks thru tubing at 2200' + from surface

Name of Plugging Contractor: DS&W Well Servicing License #: 6901  
Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.  
State of Kansas County, Barton, ss.

Jacob Porter (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter  
(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 21st day of June, 20 05

Elaine Schreck My Commission Expires: 12-13-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN 22 2005  
KCC WICHITA

CARMEN SCHMITT INC  
OGALLAH UNIT 7-7  
PLUGGING

6-08-05

M.I.R.U. D.S. & W. WELL SERVICE. L-K WIRELINE PER 920 FT AND 1750 FT. TO PLUG. RAN 2-3/8 TUBING TO 2200 FT. ALLIED CEMENTING MIXED 75 SKS OF 60-40 POZ, AND 10 % GEL. CIRCULATED CEMENT. PULLED TUBING OUT. HOOKED UP ON SURFACE PIPE, TOOK 5 BBLs TO LOAD. PRESSURED TO 1500 P.S.I. HOOKED BACK UP ON 5-1/2. MIXED ANOTHER 150 SKS WITH 600 HULLS. MAX PRESSURE WAS 500 LBS. SHUT WELL IN AT 300 P.S.I. ROGER MOSES WITH KCC WITNESSED JOB

RECEIVED

JUN 22 2005

KCC WICHITA