

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.  
Address: PO Box 47, Great Bend, KS 67530  
Phone: (620) 793-5100 Operator License #: 6569  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6/9/05 (Date)  
by: Roger Moses (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3983 Bottom: 4010 T.D. 4010  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-00812-00-00  
Lease Name: Ogallah Unit  
Well Number: 7-3  
Spot Location (QQQQ): NE-SW-SW  
990 Feet from  North /  South Section Line  
4290 Feet from  East /  West Section Line  
Sec. 25 Twp. 13 S. R. 22  East  West  
County: Trego  
Date Well Completed: Jan 1952  
Plugging Commenced: 6/9/05  
Plugging Completed: 6/9/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		<u>0</u>	<u>498</u>	<u>8 5/8"</u>	<u>Jan 1952</u>	
		<u>0</u>	<u>3983</u>	<u>5 1/2"</u>	<u>Jan 1952</u>	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


see attached report  
~ 300 sks in 2 plugs thru tubing at 2200' and 1100', + from surface

Name of Plugging Contractor: DS&W Well Servicing License #: 6901  
Address: PO Box 231, Claflin, KS 67525

Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.  
State of Kansas County, Barton, ss.

Jacob Porter (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L Porter  
(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 21st day of June, 20 05

Elaine Scheck My Commission Expires: 12-13-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN 22 2005  
KCC WICHITA

CARMEN SCHMITT INC  
OGALLAH UNIT 7-3  
PLUGGING

06-09-05

M.I.R.U. D.S. & W WELL SERVICE. RIGGED UP L-K WIRELINE TO PERF. RAN IN HOLE TO PERF, STACKED OUT AT 630 FT. RIGGED UP AND RAN TUBING AND A 2-1/2 SWEDGE IN HOLE. RAN DOWN THROUGH BRIDGE. RAN TUBING TO 1200 FT. STACKED OUT. WORKED TUBING UP AND DOWN. FELL THROUGH AND RAN TUBING TO 2200 FT. LAID TUBING BACK OUT. L-K RIGGED UP AND PERF. 920 AND 1750 FT. RAN TUBING BACK TO 2200 FT. TO PLUG. ALLIED MIXED 100 SKS OF 60-4- POZ, 10 % GEL, AND 2 BAGS OF HULLS. PUMPED DOWN TUBING. PULLED TUBING TO 1100 FT. CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT. PUT SWEDGE ON 5-1/2 AND FINISHED PLUGGING WELL. SHUT WELL IN WITH 400 P.S.I. USED 600 HULLS AND 300 SKS OF CEMENT ON 5-1/2 AND 10 SKS ON SURFACE. SHUT SURFACE PIPE IN WITH 200 P.S.I. ROGER MOSES WITH KCC WITNESSED JOB.

RECEIVED  
JUN 22 2005  
KCC WICHITA