

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Carmen Schmitt Inc.  
Address: PO Box 47, Great Bend, KS 67530  
Phone: (620) 793-5100 Operator License #: 6569  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 5/24/05 (Date)  
by: Royer Moses (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3988 Bottom: 4014 T.D. 4014  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-01451-00-00  
Lease Name: Ogallah Unit  
Well Number: 4-2  
Spot Location (QQQQ): - SE - NW - SE  
1650 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 26 Twp. 12 S. R. 22  East  West  
County: Trego  
Date Well Completed: August 1951  
Plugging Commenced: 5/24/05  
Plugging Completed: 5/24/05

Show depth and thickness of all water, oil and gas formations.


| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |      |        |          |            |
|---------------------------|---------|--|------|--------|----------|------------|
| Formation                 | Content | From   | To   | Size   | Put In   | Pulled Out |
|                           |         | 0  | 236  | 8 5/8" | Aug 1951 |            |
|                           |         | 0  | 3992 | 5 1/2" | Aug 1951 |            |
|                           |         |  |      |        |          |            |
|                           |         |  |      |        |          |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

see attached report  
~ 300 sks thru tubing at 2200' and 1100' + from surface.

Name of Plugging Contractor: DS&W Well Servicing License #: 6901  
Address: PO Box 231, Claflin, KS 67525  
Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc.  
State of Kansas County, Barton, ss.  
Jacob Porter

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L. Porter  
(Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 21st day of June, 20 05  
Elaine Scheck My Commission Expires: 12-13-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN 22 2005  
KCC WICHITA

CARMEN SCHMITT INC  
OGALLAH UNIT 4-2  
PLUGGING

5-24-05

M.I.R.U. D. S. & W. WELL SERVICE. L-K WIRELINE PERF 920 FT AND 1750 FT. RAN TUBING TO 2200 FT. PUMPED 100 SKS OF 60-40 POZ, 10 % GEL, AND 300 HULLS. PULLED TUBING TO 1100 FT AND MIXED 100 SKS CEMENT AND 200 HULLS. LAID TUBING DOWN AND HOOKED UP ON SURFACE PIPE. PUMPED 5 SKS AND PRESSURED TO 1500 P.S.I. TIED BACK ON 5-1/2 AND MIXED 100 SKS OF CEMENT WITH 100 HULLS. PRESSURED TO 300 P.S.I. USED 305 SKS CEMENT AND 600 HULLS. ROGER MOSES WITNESSED JOB.

RECEIVED  
JUN 22 2005  
KCC WICHITA