

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

15-065-00311-00-00

WELL PLUGGING RECORD

T 7S NORTH R 22W

		15	
*			

Locate well correctly on above  
Section Plat

Graham

County. Sec. 15 Twp. 7S Rge. 22W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SW NW SW

Lease Owner Lawrence Supply Company

Lease Name Davis Well No. 1

Office Address Box 448 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed October 30 19 52

Application for plugging filed Decmeber 8 19 55

Application for plugging approved December 9 19 55

Plugging commenced December 9 19 55

Plugging completed December 16 19 55

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production November 19 55

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3874 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	198'	None
				5-1/2"	3750'	1696'
				Plug set at 3700' and casing perforated from 3693' to 3697'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3000' to 3690' and ran 4 sacks of cement. Mudded the hole to 190', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas COUNTY OF Barton ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. I. B. Lawrence

(Signature) Lawrence


P.O. Box 448, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of December, 1955

Sidney D. Miller  
Notary Public.

My commission expires 24 October 1956



12/22/55